



**Universiteit
Gent**

**Testcentrum
VOOR
Gevelementen**

TEST REPORT NR. 828/0044

TEST CARRIED OUT IN ACCORDANCE WITH

STS 52.0 EDITION 1985

**ON AN ALUMINIUM CURTAIN WALL SERIE MC
WITH THERMAL BREAK.**


UNIVERSITEIT GENT
TESTCENTRUM VOOR GEVELELEMENTEN
DIENST: PROF. DR. IR. R. SIERENS
.....

9000 GENT, 99-04-27
SINT-PIETERSNIEUWSTRAAT 41
TEL (09) 264 33 59
FAX (09) 264 35 90

TEST REPORT NR: 828/0044

TEST CARRIED OUT ON AN
AN ALUMINIUM CURTAIN WALL SERIE MC
WITH THERMAL BREAK

OF THE COMPANY:
ALIPLAST ALUMINIUM SYSTEMS



APPLICANT:

.....
ALIPLAST ALUMINIUM SYSTEMS

Waaslandlaan 15
9160 LOKEREN

Contact: mr. Coeymans M.
Phone: 09 340 55 55

2 MANUFACTURER:

.....
ALIPLAST ALUMINIUM SYSTEMS

Waaslandlaan 15
9160 LOKEREN

Phone: 09 340 55 55

3 DESTINATION: atg Butgb

4 MATERIAL SENT FOR TEST:

4.1. Identification of the test element:

Test element supplied by the applicant on 99-04-27 and in accordance with the included drawing with ref. nr.: 828/0044
Drawing certified with the stamp:

4.2. Dimensions of the test element:

width : 3.20 m
height : 3.38 m
total surf.: 10.816 m²
length of the opening joints: 5.20 m
surface of the opening light frame: 1.632 m²

**
* UNIVERSITEIT GENT *
TESTCENTRUM VOOR *
GEVELELEMENTEN *
Sint-Pietersnieuwstraat 41 *
B-9000 GENT (BELGIE) *

4.3. Description of the parts of the test element:

Sections:

material : aluminium with thermal break
type : see drawing ref. nr. 828/0044
surface treatment : laquered
type of connection: glued, pressed and screwed

Tightening strips:

material: epdm
type : see drawing ref. nr. 828/0044
place : see drawing ref. nr. 828/0044

Glass:

thickness : double 6+12+6 mm
type : not indicated
way of glazing: pre-fabricated profils

Fittings:

hinges: mark : Rivalu
type : Italincox 7000
number: 2

closing fittings: mark: Rivalu
type: Italincox 7000
closing fittings: mark:
number of locking points: 5

Drainage:

of the glazing : see drawing ref. nr. 828/0044
of the opening joint: see drawing ref. nr. 828/0044

Ventilating of the opening joint: see drawing ref. nr. 828/0044

5 INSTALLATION IN THE TEST CENTER:

.....
The element to test is fixed on the test chamber in accordance with
the included drawing nr.: 828/0044 and scheme 828/1/1.
Air temperature in the test chamber: 20.0 °C
Air temperature in the test center : 20.0 °C

TESTS CARRIED OUT: see scheme 828/1/2

6.1. Air permeability in accordance with NBN B 25-204:

6.1.1. Positive pressure see fig. 828/0044 /1

Pres- sure. Pa	Air permeability m ³ /h	Per m opening joint m ³ /hm	Per m ² opening surf. m ³ /hm ²	Per m ² tot. surface. m ³ /hm ²
50.	2.480	0.477	1.519	0.229
100.	4.607	0.886	2.822	0.426
150.	6.344	1.220	3.885	0.586
200.	7.717	1.484	4.728	0.713
300.	10.228	1.967	6.267	0.946
400.	10.015	1.926	6.136	0.926
500.	8.804	1.693	5.394	0.814
600.	11.741	2.258	7.194	1.085
500.	9.963	1.916	6.103	0.921
400.	9.324	1.793	5.712	0.862
300.	8.382	1.612	5.136	0.775
200.	6.193	1.191	3.793	0.572
150.	5.793	1.114	3.547	0.536
100.	4.488	0.863	2.750	0.415
50.	2.688	0.517	1.648	0.248

6.1.2. Negative pressure see fig. 828/0044 /1

Pres- sure. Pa	Air permeability m ³ /h	Per m opening joint m ³ /hm	Per m ² opening surf. m ³ /hm ²	Per m ² tot. surface. m ³ /hm ²
50.	2.454	0.472	1.503	0.227
100.	4.628	0.890	2.836	0.428
150.	6.531	1.256	4.001	0.604
200.	8.403	1.616	5.146	0.777
300.	12.079	2.323	7.401	1.117
400.	15.480	2.977	9.482	1.431
500.	19.630	3.775	12.025	1.815
600.	22.874	4.399	14.012	2.115
500.	18.647	3.586	11.424	1.724
400.	14.913	2.868	9.136	1.378
300.	12.105	2.328	7.414	1.119
200.	8.788	1.690	5.385	0.812
150.	6.911	1.329	4.232	0.639
100.	4.992	0.960	3.060	0.461
50.	2.834	0.545	1.737	0.262

REMARKS: none.

6.2. Testing the wind resistance in accordance with NBN B 25-205:

6.2.1. Deformation test by positive pressure measured over a length of 0.88 m in point B see fig. 828/0044 /2:

Pressure Pa	Deformation point B mm
0.	0.0
100.	0.0
200.	0.1
300.	0.2
400.	0.3
500.	0.3
600.	0.4
750.	0.5
1000.	0.7
1750.	1.3

Permanent deformation: 0.0 mm

RESULT: the element is satisfactory.

6.2.2. Deformation test by negative pressure measured over a length of 0.88 m in point B see fig. 828/0044 /2

Pressure Pa	Deformation point B mm
0.	0.0
100.	0.0
200.	0.1
300.	0.2
400.	0.3
500.	0.3
600.	0.4
750.	0.5
1000.	0.7
1750.	1.3

Permanent deformation: 0.0 mm

RESULT: the element is satisfactory.

6.2.3. Repeated positive and negative pressure test from 0 to 1250. Pa (250 cycles positive and 250 cycles negative).

6.2.4. Safety test with a positive pressure of: 3000. Pa

RESULT:

There was no damage or faulty operation after the test.

6.2.5. Safety test with a negative pressure of: 3000. Pa

RESULT:

There was no damage or faulty operation after the test.

6.3. Control of the air permeability in accordance with NBN B 25-204:
(After test 6.2. the wind resistance.)

6.3.1. Positive pressure see fig 828/0044 /1:
Difference in air permeability expressed in percentage and in
 m^3/hm opening joint in relation to test 6.1.1.

Pres- sure Pa	Difference air permeability %	per m opening joint m^3/hm
50.	-1.240	-0.006
100.	-0.960	-0.009
150.	1.584	0.019
200.	0.170	0.003
300.	-13.809	-0.271
400.	11.713	0.226
500.	0.261	0.005
600.	0.927	0.021
500.	1.286	0.024
400.	-3.845	-0.069
300.	-2.384	-0.038
200.	-4.050	-0.049
150.	-3.384	-0.038
100.	-1.012	-0.009
50.	-4.298	-0.022

6.3.2. Negative pressure see fig 828/0044 /1:
Difference in air permeability expressed in percentage and in
 m^3/hm opening joint in relation to test 6.1.2.

Pres- sure Pa	Difference air permeability %	per m opening joint m^3/hm
50.	4.744	0.022
100.	4.323	0.039
150.	4.267	0.054
200.	4.451	0.071
300.	4.130	0.096
400.	2.481	0.073
500.	7.824	0.295
600.	4.681	0.206
500.	6.965	0.250
400.	10.696	0.307
300.	4.557	0.106
200.	4.241	0.072
150.	5.245	0.069
100.	4.765	0.046
50.	3.307	0.018

6.3.3. Conservation of the qualities:

The air permeability measured after the wind resistance test may not be higher than 20 % (with a minimum of $0.3 m^3/hm$ opening joint) of the air permeability measured before the wind resistance test.

RESULT: the element is satisfactory.

6.4. Watertightness test in accordance with NBN B 25-209:

6.4.1. Under static air pressure:

Pressure Pa	Duration min.	Remarks
0	15	no infiltration
50	5	no infiltration
100	5	no infiltration
150	5	no infiltration
200	5	no infiltration
300	5	no infiltration
400	5	no infiltration
500	5	no infiltration
600	5	no infiltration
700	5	no infiltration
800	5	no infiltration
900	5	no infiltration
1000	5	no infiltration

6.4.2. Under dynamic air pressure:

50 pulsations are carried out between 0 + 50 Pa and 700 + and - 50 Pa:
no infiltration

6.5. Mechanical tests in accordance with NBN B 25-210:

REMARKS:
TESTS NOT CARRIED OUT.

EVALUATION:

.....
7.1. In accordance with STS 52.0:
results for

- air permeability : PA3
- wind resistance : PV2
- watertightness : PEE 1000 Pa

7.2. In accordance with UEATC:
class for


- air permeability : A3
- wind resistance : V2
- watertightness : E4


8 REMARKS:

.....
8.1. The results are only valid under the conditions as ruling during
the test.

8.2. This report is only valid when showing the reference number and
stamp on all annexes.

8.3. Partial copy of this report is not allowed without written consent
of Prof. Dr. Ir. R. SIERENS, director of the "Testcentrum voor
Gevelelementen".


R. HUWEL
Engineer responsible for the tests.


Prof. Dr. Ir. R. SIERENS
Director.

ANNEXES:

..... with stamp

Drawings nr.

828/1/1

828/1/2

Figures nr.

828/0044/1 - 2

UNIVERSITEIT GENT
TESTCENTRUM VOOR
GEVELEMENTEN
Sint-Pietersnieuwstraat 11
B-9000 GENT (BELGIË)


Measuring
the flow

WATER


MEASURING THE
Flow Pressure

Test chamber


AIR



PRESTATIE NIVEAU	PA2 500	300	-500	-300	PV1 500	500	-600	-600	450	-450
	PA2 550	500	-550	-500	PV1B 750	750	-750	-750	600	-600
	PA3 660	600	-660	-600	PV2 1000	1000	-1000	-1000	750	-750
					PV3 1000max	1000max	-1000max	-1000max	10max	-10max



PRESTATIE NIVEAU	PA2 500	300	-500	-300	PE2 500	150	(250)	PV1 1000	-1000
	PA2 550	500	-550	-500	PE3 500	300	(250)	PV2 500	-1500
	PA3 660	600	-660	-600	PE4 550	500	(250)	PV3 1000	-2000
					PEE 10max	10max	(250)	PV4 1000max	




MECHANICAL TEST
NBN B25.206


TEST VI

AIR PERMEABILITY IN ACCORDANCE WITH NBN B25-204

POSITIVE PRESSURE



NEGATIVE PRESSURE





Ref. nr. 828/0044/1

Date: 99-04-27

UNIVERSITEIT GENT
TESTCENTRUM VOOR
GEVELEMENTEN
Sint-Pietersnieuwstraat 41
B-9000 GENT (BELGIE)

WIND RESISTANCE IN ACCORDANCE WITH

NBN B25-205











Ref. nr. 828/0044/2












Date: 99-04-27

UNIVERSITEIT GENT
TESTCENTRUM VOOR
GEVELEMENTEN
Sint-Pietersnieuwstraat 41
B-9000 GENT (BELGIE)


PLYWOOD IS GLUED UNASSAILABLE FOR WATER



PLYWOOD IS GLUED UNASSAILABLE FOR WATER



SCALE : 1/20



Product information table for Allplast 151 Wall Inc. including model numbers, dimensions, and contact information.